DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

INTERDEPARTMENT CORRESPONDENCE

FILE:

STPN0-0007-03(033), Lowndes County

OFFICE: Engineering Services

P.I. No. 422710

US 84/SR 38 @ Norfolk Southern RR

DATE: April 14, 2009

FROM:

Ronald E. Wishon, State Project Review Engineer Rew

TO:

Brent A. Story, P.E., State Road Design Engineer

Attention: Tim Matthews, Project Manager

SUBJECT: IMPLEMENTATION OF VALUE ENGINEERING STUDY ALTERNATIVES

Recommendations for implementation of Value Engineering Study Alternatives are indicated in the table below. Incorporate alternatives recommended for implementation to the extent reasonable in the design of the project.

ALT No.	Description	Savings PW & LCC	Implement	Comments
		ROADWAY	<i>Y</i>	
A-4	Eliminate the sidewalk on the south side (right) of the W. Hill Avenue mainline roadway through the entire elevated section.	\$246,000	No	In order for pedestrians to cross the bridge from the south side they would have to travel on the frontage road an additional ~ 1/4 mile. Once on the north side of W. Hill Avenue, they can continue across the bridge. In order to get back on the south side, they would have to travel another ~1/2 mile. Additionally, pedestrians may attempt to cross the Rail Road at grade to avoid the distance. Therefore, it is recommended that we keep the sidewalk on the south side of W. Hill Ave.
A-6	Eliminate the right turn lane from westbound W. Hill Avenue into Wells Street.	\$60,500	Yes	This should be done.

STPN0-0007-03(033), Lowndes County

P. I. No.: 422710

VE Study Implementation Page 2.

		BRIDGE	Σ	
C-1	Use 60-inch Steel girders in-lieu-of BT-63 pre-stressed concrete girders to construct the W. Hill Avenue railroad overpass bridge.	\$100,000	No	The cost estimate for the current design is not correct as listed in the VE report. Using the same unit cost for the MSE walls as was used for the VE concept estimate (\$44.67), the MSE wall cost for the current design would be about \$1,822,000. This would make the cost of the Current Design \$4,122,000 versus \$4,786,531 for the VE Concept. Also, steel bridges are very costly to maintain compared to concrete. The additional maintenance costs of the steel bridge were not accounted for in the VE estimate.
C1.1	Use smaller BT-54 pre-stressed concrete beams in-lieu-of larger BT-63 pre-stressed concrete beams to construct the W. Hill Avenue railroad overpass Bridge.	\$200,000	No	The current design optimizes the beam spacing of the BT-63 for the most efficient structure. Using smaller beams increases the construction time by requiring more formwork between beams for the deck, diaphragms, edge beams, etc. This increased construction time was not accounted for in the VE estimate. The use of the smaller beams also results in a structure which is less than desirable.

STPN0-0007-03(033), Lowndes County

P. I. No.: 422710

VE Study Implementation

Page 3.

		ROADWA	Y	
D-1	Use a thinner pavement section for all frontage roads and side / cross streets in lieu-of the same pavement design as the W. Hill Avenue mainline pavement.	\$295,000	Yes	This should be done. A pavement design analysis will be evaluated through GDOT's pavement design review process for final approval. Once the soil survey report is complete, the SSF will also indicate any additional reduction in thickness. If OMR determines this cannot be implemented, Project Manager should request a reversal of the recommendation.
D-3	Eliminate the New South Thomas Street Connector between W. Hill Avenue and the new One Way South Frontage Road.	\$365,000	Yes	This should be done. If during the Public Hearing Process this cannot be implemented, the Project Manager should request a reversal of the recommendation.
D-8	Make both sides of the Wells Street / W. Hill Avenue intersection right-in / right-out only.	(-\$7,000)	Yes	This should be done.
D-10	Realign the West Street / W. Hill Avenue intersection to meet at a 90 degree Angle.	\$70,000	No	In order to replicate this design, we would have to use a horizontal curve of 200' or less. After reviewing the AASHTO's guidelines for "Geometric Design of Very Low-volume Local Roads, (ADT<400)", this option is not achievable because the ADT in 2033 is 800. Additionally, using a larger curve would impact historic properties to the north which are not impacted now.

STPN0-0007-03(033), Lowndes County

P. I. No.: 422710

VE Study Implementation

Page 4.

	I	ROADWAY Coi	ntinued	
J-1	Increase the inlet spacing on the new W. Hill Avenue overpass approaches and combine the storm drains into a single trunk line.	Proposed= \$40,000 Actual= \$42,540	Yes	This should be done.
J-1	Combine the storm drains on the W. Hill Avenue overpass approaches into a single trunk line with the original inlet spacing.	Proposed= \$30,000 Actual= \$32,053	No	Since J-1 will be implemented.

The Office of Engineering Services concurs with the Project Manager's responses.

Approved: Oll Mile Date: 41669

Gerald M. Ross, P. E., Chief Engineer

REW/DMF

Attachments

Brent Thomas

c:	Genetha Rice-Singleton	Tim Warren
	Brent Story	Bill Cooper
	Andy Casey	Van Mason
	Tim Matthews	Joe Cowan
	Daniel Sabia	Scott Chambers
	Paul Liles	Jerry Hughes
	Bill Ingalsbe	Ken Werho
	Bill DuVall	Lisa Myers
	Vince Wilson	Douglas Fadool
	Bobby Dollar	General Files
	Joe Sheffield	

DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA

INTERDEPARTMENT CORRESPONDENCE

FILE STPN0-0007-03(033), Lowndes County

OFFICE Road Design

P.I. No. 422710

US 84/SR 38 @ Norfolk Southern RR

DATE

April 13, 2009

FROM

Brent A. Story, P.E., State Road Design Engineer

TO

Ronald E. Wishon, Project Review Engineer

SUBJECT

Value Engineering Study Report Response

This office has received and reviewed the recommendations of the Value Engineering Study Workshop Report dated March 24, 2009. Below are our responses to the recommendations:

Alternatives:

Idea A-4: Eliminate the sidewalk on the south side (right) of the W. Hill Avenue mainline roadway through the entire elevated section:

This alternate is not recommended for implementation.

• In order for pedestrians to cross the bridge from the south side they would have to travel on the frontage road an additional ~ 1/4 mile. Once on the north side of W. Hill Avenue, they can continue across the bridge. In order to get back on the south side, they would have to travel another ~1/2 mile. Additionally, pedestrians may attempt to cross the Rail Road at grade to avoid the distance. Therefore, it is recommended that we keep the sidewalk on the south side of W. Hill Avenue. It is noted in "Designing Pedestrian Facilities for Accessibility" that Pedestrians will cross where it's most convenient. If the distance to travel seems out of reach, pedestrians will cross midblock which is a serious safety risk.

Idea A-6 Eliminate the right turn lane from westbound W. Hill Avenue into Wells Street:

This alternate is recommended for implementation.

- When the design speed is less than 45 mph the following criteria is considered for right turn lane need:
 - o Traffic on the mainline exceeds 10,000 vpd
 - Right turn volumes from mainline exceeding 20 vph and traffic volume on the side road exceeds 200 vpd.

The traffic on W. Hill Avenue and N. Wells Street does not exceed this range.

Idea C-1 OPTION 1 Use 60-inch Steel girders in-lieu-of BT-63 pre-stressed concrete girders to construct the W. Hill Avenue railroad overpass bridge:

This alternative is not recommended for implementation.

• The cost estimate for the current design is not correct as listed in the VE report. Using the same unit cost for the MSE walls as was used for the VE concept estimate (\$44.67), the MSE wall cost for the current design would be about \$1,822,000. This would make the cost of the Current Design \$4,122,000 versus \$4,786,531 for the VE Concept. Also, steel bridges are very costly to maintain compared to concrete. The additional maintenance costs of the steel bridge were not accounted for in the VE estimate.

Idea C-1.1 OPTION 2 Use smaller BT-54 pre-stressed concrete beams in-lieu-of larger BT-63 pre-stressed concrete beams to construct the W. Hill Avenue railroad overpass bridge:

This alternative is not recommended for implementation.

• The current design optimizes the beam spacing of the BT-63 for the most efficient structure. Using smaller beams increases the construction time by requiring more formwork between beams for the deck, diaphragms, edge beams, etc. This increased construction time was not accounted for in the VE estimate. The use of the smaller beams also results in a structure which is less than desirable.

Idea D-1 Use a thinner pavement section for all frontage roads and side / cross streets in lieu-of the same pavement design as the W. Hill Avenue mainline pavement:

This alternative is recommended for implementation.

- The VE team recommends using the following:
 - o 1.5" 12.5 mm
 - o 2" 19 mm
 - o 3" 25 mm
 - o 6" GAB.
- A pavement design analysis will be evaluated through GDOT's pavement design review
 process for final approval. Once the soil survey report is complete, the SSF will also
 indicate any additional reduction in thickness.

Idea D-3 Eliminate the New South Thomas Street Connector between W. Hill Avenue and the new One Way South Frontage Road:

This alternative will be considered for implementation.

• PM will coordinate with Stake Holders and get public feedback during Public Hearing process.

Idea D-8 Make both sides of the Wells Street / W. Hill Avenue intersection right-in / right-out only:

This alternative is recommended for implementation.

- Although this alternate increase cost by adding concrete islands, it is recommend due to safety concerns for left turn movements.
- Adding the islands would also provide better operational movements.

Idea D-10 Realign the West Street / W. Hill Avenue intersection to meet at a 90 degree angle:

This alternative is not recommended for implementation.

- In order to replicate this design, we would have to use a horizontal curve of 200' or less. After reviewing the AASHTO's guidelines for "Geometric Design of Very Low-volume Local Roads, (ADT<400)", this option is not achievable because the ADT in 2033 is 800.
- Additionally, using a larger curve would impact historic properties to the north which are not impacted now.

Idea J-1 Increase the inlet spacing on the new W. Hill Avenue overpass approaches and combine the storm drains into a single trunk line:

This alternative is recommended for implementation.

- Approximate savings = (57 lf x \$43.67/ft) (1 catch basin x \$2492.34) (385 lf x \$43.67/ft) = \$16,816.10
- Approximate savings = (140 lf x \$43.67/ft) (1 catch basin x \$2492.34) (672 lf x \$43.67/ft) = \$25724.78
- Total Savings = \$42,540.88

Idea J-1.1 ALTERNATIVE to IDEA J-1 Combine the storm drains on the W. Hill Avenue overpass approaches into a single trunk line with the original inlet spacing: N/A since we are implementing J-1.

- Approximate savings = (196 lf x \$43.67/ft) (672 lf x \$43.67/ft) = \$20786.92
- Approximate savings = (127 lf x \$43.67/ft) (385 lf x \$43.67/ft) = \$11266.86
- Total savings = \$32053.78


If there are any questions or comments concerning these recommendations, please contact Tim Matthews, P.E. at (404) 631-1552.

BAS:CAC:twm

cc: Director of Preconstruction
Lisa Myers, Engineering Services
Tim Matthews, Road Design
Paul Liles/Pam Russell – Bridge Design
Glenn Bowman/Bobby Dollar – OEL
James Magnus – Construction
Joe Cowan/Dot Downie – District 4 Construction
Carlos Baker – TS&D

PRECONSTRUCTION STATUS REPORT FOR PI:422710-

			PRECON	ISTRUCTION	STATL	PRECONSTRUCTION STATUS REPORT FOR PI:422710-	R PI:42	2710-						
PROJ ID:	422710-	SR 38/US 84/W. HILL AVE GRADE SEPARATION @ NORFOLK SOU. RR	AVE GRADE	SEPARATION	® NORFO	LK SOU. RR		E.	MC	MGMT LET DATE		07/15/2012		
COUNTY:			MDO.	Valdosta		DOT DIST:	7		M	MGMT ROW DATE:		09/15/2010		
LENGTH (MI):		STPN0-0007-03(033)	TP#.	VL07		CONG. DIST:	e		S	SCHED LET DATE:		8/8/2012		
PROJ NO.:			MODEL YR:			BIKE:		z	M	WHO LETS?:	99	GDOT Let		
PROJ MGK:			TYPE WORK:	Bridges		MEASURE:		ш	H	LET WITH:				
CONSULTANT:		t, GDOT In-House Design	CONCEPT:	GRADE SEP		NEEDS SCORE:		90						
SPONSOE .	GDOT		PROG TYPE:	New Construction		BRIDGE SUFF:	JFF:							
DESIGN FIRM:	IM:	4	Prov. for ITS:	z										
		8	BOND PROJ:											
SCHED	SCHED	ACTIVITY	ACTUAL	ACTUAL FINISH	%			PROGRAN	PROGRAMMED FUNDS	Fund	Status	Date Auth		
		Concept Development	5/15/2002	5/19/2005	100	rhase A	Approved 2001	2001	1 500 000 00		AUTHORIZED			
		Concept Meeting	9/10/2003	9/10/2003	001	*	2008	2010	8,151,688.00	_	PRECST			
		PM Submit Concept Report Receive Preconstruction Concept Approval	4/28/2005	5/10/2005	100		NONE		87,880.00		PRECST			
		Management Concept Approval Complete	5/13/2005	5/19/2005	100	CST	LR	LR 2	22,951,245.83	LOSO PRE	PRECST			
	5/5/2009	Value Engineering Study	12/2/2008		94						CTID	STINIOW GITS		
	6	Public Information Open House Held	9/15/2004	9/16/2004	001	PE Cost Est Amt:		Date:		i	, and			
0002/11/6	4/8/2010	Environmental Approval Pub Hear Held/Comm Resn (FA/FONS). GFPA)	/007/1/0		0	ROW Cost Est Amt	7,0	7,618,400.00 Date:	1/6/2009	Fuase	,	Cost	Fund	
		Field SurveySDE	6/20/2005	11/16/2005	100	Utility Cost Est Amt		87,880.00 Date:	1/6/2009	7			070	
	8/13/2009	Preliminary Plans	9/4/2006		26	CST Cost Est Amt	14.0	14,090,074.00 Date:	2/10/2009	ROW	4,55		1.050	
		Preliminary Bridge Design	3/28/2007	11/8/2007	100					75			TOC	
		Underground Storage Tanks	10/22/2004	2/17/2009	100					CST		0.00	1.050	
0	5/3/2010	PFPR Inspection			0 0									
_	7/26/2010	R/W Plans Preparation			.									
	0102//2/8	K/W Plans Final Approval			• 0									
8/30/2010	6/12/2010	R.W. Acquisition			0									
	2/2/2011	Stake R/W			0									
4/24/2009	12/8/2009	Soil Survey			0									
4/24/2009	1/26/2010	Bridge Foundation Investigation			0									
6/14/2010	7/11/2011	Final Design			5									
	12/17/2009	Final Bridge Plans Preparation	4/29/2008		2 ⊂									
8/17/2011	8/30/2011	Submit FFPR Responses (OES)			0									
PDD:	ASSIGNED	ASSIGNED TO ROAD DESIGN. 7/21/99.							District Com	ments.	007.64			
Bridge:	PSR 11/03/08	80				PE PROJ NO: PESTP000703033., (1) sent extra survey data on top of rati into on 1/03/08.	000703033	, (1) sent extra surve	y data on top of	rail into on I/A	75/08.			
Design:	TWM/JT/D	TWM/JT/DS-Working PREL. PLANS (4-2009)												
EIS:	VAL DOST	EA]NOIApvd[OnSchedKW]Updatcd4-6-09[Dollar VALDOSTA SON DO 11711 1711657-25-09]RESCISSION LETTER SENT TO VALDOSTA 6-8-05.	ENT TO VALDO	STA 6-8-05.										
Leff A:	>3-6-09-PB	>3-6-09-PB: working on sign/mark												
UST:	SUB TO OF	SUB TO OMR 01-27-03 (2 SITES) 10-22-04 (4 SITES)												
Utility: EMG:	REV-EST.	REV-EST, SUB, 04/11/2005 SUE QL-B compl 2-11-08 GRADE SEPARATION (BRIDGES)												
Prel. Parcel CT:		Total Parcel in ROW System:	Conc	Cond. Filed:		Acqui	Acquired by:	TOO				DEEDS CT:		
Under Review:	22%	Options - Pending:	Relo	Relocations:		Acqui	Acquisition MGR:	R:						
Released.		Condemnations Pend:	Acqu	Acquired:		R/W	R/W Cert Date:							



M:\422710\DGN\\422710\CV01.dgn 4/13/2009 3:09:59 PM